




**ADDENDUM NO. 1
TO
PROJECT MANUAL
SPECIFICATIONS
FOR
CITY OF ANTIOCH
MARINA BOAT LAUNCH FACILITY RESTROOM
IN
ANTIOCH, CALIFORNIA
P.W. 523-16R**

**ISSUED
January 30, 2013**

This Addendum No. 1 must be signed by the bidder and attached to the CONTRACT PROPOSAL PACKAGE for consideration by the City. The City reserves the right to disregard any proposal, which does not include this Addendum. The City may waive this requirement at its sole discretion.

SEE ATTACHED ADDENDUM ITEMS

Prepared By: 
Scott Buenting, P.E.

BIDDER'S CERTIFICATION

I acknowledge receipt of this Addendum No. 1 and accept all conditions contained herein.

Bidder

By:

Section 16010, "General Electrical Requirements", Subsection 1.01, "Work Included", Subsection C, "Scope of Work" is amended to include the following:

9. Contractor shall provide temporary lighting for the parking lot and launch ramp for the duration of the period during which existing light fixtures in these areas would otherwise be out of service due to the relocation of existing panelboards and lighting controls into the new restroom facility.

Temporary lighting shall be operational from dusk to dawn, during the hours the existing lighting fixtures would normally be operational, or as otherwise directed by the City.

Temporary lighting shall provide a minimum average illumination level of 0.5 footcandles on the pavement for both the parking lot and ramp areas, with adequate coverage and uniformity to ensure these areas are safe for public use. Temporary lighting, at the Contractor's option, may be affected through provision of a temporary generator, temporary electrical panelboard and wiring in combination with existing electricals, or by provision of standalone temporary lighting units. All temporary lighting equipment and installations, including wiring, shall be provided, maintained and operated by the Contractor, shall comply with applicable safety codes and requirements, and shall be installed, maintained, and operated in a manner to ensure public safety.

Submit the following for the City's review before construction commences:

- a. Temporary lighting plan
- b. Description of proposed equipment
- c. Proposed equipment installation plan and locations
- d. Calculated lighting levels if the existing lighting is not used,
- e. Proposed plan to ensure equipment remains in operation during hours temporary lighting system is required to be in operation
- f. Proposed safety precautions to ensure public safety
- g. Emergency response plan in the event temporary lighting system maintenance is necessary.