

Title: Water Main Replacement on North Lake Drive and North Lake Circle in Antioch, CA (P.W. 503-12)
 Bids to be received by 2:00 p.m. September 6, 2011
 Office of the City Clerk, City Hall, Antioch, CA

SCHEDULE OF BID PRICES

Item No.	Unit	Quantity	Description	Unit Price	Extended Amount
1.	LS	1	Mobilization, complete in place for the lump sum price	\$	\$
2.	LS	1	Traffic control, complete in place for the lump sum price	\$	\$
3.	LS	1	Erosion control, complete in place for the lump sum price	\$	\$
4.	LF	660	New 8-inch C-900 PVC water main, including valves and fittings, complete in place for the unit price per lineal foot	\$	\$
5.	LF	1,400	New 10-inch C-900 water main, including valves and fittings, complete in place for the unit price per lineal foot	\$	\$
6.	EA	42	New 1-inch copper water service, complete in place for the unit price per each	\$	\$
7.	EA	4	Remove and replace fire hydrant, including 6-inch C-900 hydrant stubs, new valves and fittings, complete in place for unit price per each	\$	\$
8.	SF	18,700	Cold planing asphalt concrete, complete in place for the price per square foot	\$	\$
9.	TN	350	Asphalt concrete, complete in place for the unit price per ton	\$	\$
10.	LS	1	Thermoplastic Traffic Stripes, Pavement Markers and Pavement Markings, complete in place for the lump sum price	\$	\$
TOTAL BID PRICE				\$	\$

TOTAL BID PRICE:

(Written in Words)

All costs associated with the work required in the Plans and Specifications must be included in the bid items. This certifies that the prices in the proposal include all work as shown in the Plans and Specifications necessary to complete the work, in place and in full working order.

Signature of Bidder

Company Name Printed